



PROJECT INFORMATION

Project Name: St. Vladimir - Dome
Recoat

Project Year: 2025

Project Size: Roof = 10,000 sq. ft.

Project Location: Parma, OH

Days to Complete: 12

Project Overview: Acrylic base/top coat
over existing coating

Manufacturer Used: Sherwin-Williams

Warranty (Roof): 10 years, Full System,
NPR, NDL, renewable contractor's
warranty.

St. Vladimir Church has been in Parma, Ohio since 1957.

West Roofing Systems came into the picture when we installed a spray foam roof on the structure in 1993.

The roof was recoated with acrylic in 2003. 22 years later, the 2nd recoat was installed.

The roof has an internal gutter system that was holding water.

We increased the slope of the gutter system and applied a high-solids silicone coating to withstand the large volume of water draining from this roof.

An acrylic base coat and intermediate coat were applied to the roof field, with a total thickness of 20 dry mils.

A tinted topcoat was applied to provide a glossy finish using Sherwin-Williams Sher-Cryl.



